

# DINH VU WAREHOUSE VIETNAM USE DRAMIX 5D FOR SLAB ON PILE

Dramix 5D Slab on Piles cost effective solution for warehouse at Dinh Vu, Hai Phong.

The new renting warehouse for WWWHP (World Wide Warehouse Hai Phong) in Dinh Vu, is designed as a Slab on Pile to carry 4t post loads from the racking system and a UDL of up to 3t/m2.

The Dramix 5D Slab on Pile solution was chosen as the most cost effective solution, with a reduction in the slab thickness and removing up to 90% of the traditional reinforcing.

### Technical solution

- Dramix 5D + edge mesh
- Jointless – No Saw Cuts
- 40Mpa

### Benefits

Utilising a Dramix 5D slab on Pile solution offered the client:

- A thinner slab
- Slab with significantly reduced number of joints
- Removal of all saw cuts
- Speed of construction
- Overall reduced long term maintenance costs

CALL 1300 665 755 (AUS) OR 0800 665 755 (NZ)  
VISIT BOSFA.COM

