

GIANT DISTRIBUTION CENTER SEPANG, MALAYSIA

Dramix Slab on Pile the only solution for Giant Distribution

This is the first Dramix slab on pile project in Malaysia. Pile spacing is 3.2m x 3.2m grid, the slab is resting on 200mm x 200mm square pile. No pile caps are required for the construction of the slab. The floor is constructed by Asia Powermix with TK Flat Floor Malaysia.

Technical solution

- Slab on Pile
- No pile cap required
- Dramix 5D

Benefits

The placement of 14,400sqm was reduced from 3 months to just 1 month. Cost and time savings for the builder.

CALL 1300 665 755 (AUS) OR 0800 665 755 (NZ)
VISIT BOSFA.COM

