

LOGISTICS WAREHOUSE BREEZEWAY

Saw Cut Free Breezeway

This was a breezeway pavement for a logistics warehousing facility with container and forklift loads. Dramix 4D Combi Slab was used to remove all the saw cuts and the inherent ongoing maintenance cost associated with saw cuts having to be re-sealed and saw cuts not initiating.

Technical solution

- 35mpa concrete
- Dramix 4D 65/60BG
- Light mesh

Benefits

- Sped up construction
- Reduced slab thickness
- No saw cut joints
- Significantly reduced ongoing maintenance costs
- More cost effective than a conventionally reinforced slab
- Cost neutral compared to a fibre only reinforced slabs with sealed saw cuts

CALL 1300 665 755 (AUS) OR 0800 665 755 (NZ)
VISIT BOSFA.COM

