

CEVA VEHICLE LOGISTICS – A YEAR ON

Dramix Combi Slab at Pinkenba is already standing the test of time.

Over a year since the Dramix Combi Slabs were placed at the Ceva Vehicle Logistics facility in Pinkenba and they remain in excellent condition. The saw-cut free fully restrained Combi Slab solution was chosen to accommodate some heavy loads, along with the poor ground conditions. And whilst other areas are suffering from ground support issues, the Internal Warehouse slabs are performing perfectly with no such concerns.

Technical solution

- Dramix Combi Slab Crack Width – 0.20mm Nominal
- Dramix 4D 65/60BG with SL101 Mesh Top
- 300mm thick slab with deep edge beams
- 40MPa Concrete

Benefits

Dramix Combi Slab was able to eliminate the need for any saw-cuts whilst being fully restrained with deep beams on the column grid lines to accommodate the poor ground conditions.

Engineer: Costin Roe Consulting.

Builder: CIP – Commercial & Industrial Property Pty Ltd

Concrete Contractor: QR Contracting

Location: Pinkenba, QLD Australia

CALL 1300 665 755 (AUS) OR 0800 665 755 (NZ)

VISIT BOSFA.COM

