

## HYDRAULINK WAREHOUSE FACILITY

The slab is fully restrained through being tied into pre-cast panel walls on two sides. Using conventional methods of construction this level of restraint would have required jointing in the floor. Taking this restraint into account the Dramix® 4D CombiSlab solution enabled the construction of the floor completely joint free. This eliminated construction and, importantly, the maintenance costs associated with sawn and movement joints.

### Technical solution

- Fibre Type – DRAMIX® 4D 65/60BG
- Additional Reinforcement – top layer of mesh
- Constructed completely joint free
- C35/45 concrete
- Engineer: MSC Consultants
- Contractor: Conslab

### Benefits

- Restrained slab constructed joint free
- Reduced long term maintenance
- Improved durability and elimination of joint damage from hard wheeled forklift

CALL 1300 665 755 (AUS) OR 0800 665 755 (NZ)  
VISIT [BOSFA.COM](http://BOSFA.COM)

